


15-163-02906-00-0

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec 25 Twp 9 Rge 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE.1/4, NE.1/4, SE.1/4
Lease Owner Harbar Drilling Co.
Lease Name Scheneider Well No. I
Office Address 1019 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Notary Dry Hole
Date well completed II/26/50
Application for plugging filed II/26/50 Verbal 19
Application for plugging approved II/26/50 Verbal 19
Plugging commenced II/26/50 19
Plugging completed II/27/50 19
Reason for abandonment of well or producing formation X



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production X 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Peddy
Producing formation None Depth to top X Bottom X Total Depth of Well 3682 Feet
In Conglomerate
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sands, soils and shales	Dry	0	280'	8 5/8"	279'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from T. D. (3682) back to 175', where a wooden bridging plug was set and 15 sacks cement was dumped on top plug. Hole filled with mud from top cement back to 40' where another wooden plug was set and 10 sacks cement was dumped on top plug filling hole to top and overflowing into bottom cellar.

Surface casing was circulated with 150 sacks cement at time it was set.

STATE CORPORATION COMMISSION
DEC 1 - 1950
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbar Drilling Co.
Address 1019 Central Bldg., Wichita, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.
I, H. L. King (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. L. King*


(Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 1950

My commission expires 9-4-54

22-7377-8 4-49-10M

PLUGGING
FILE SEC 25 T 9 R 19a
BOOK PAGE 46 LINE 4



Ray Gilling
Notary Public.

15-163-02906-00-00

SCHNEIDER NO. 1

NE¹/₄ NE¹/₄ SE¹/₄ Sec. 25-9S-19W, Roaks County, Kansas

Rigging up Rotary Tools 11-16-50
Tearing down Rotary Tools 11-27-50

Run 7 Jts. 280' of 8 5/8" surface Pipe.
Set at 279' and cemented with 150 sx cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay and sand	0	40
Sand and shale	40	280
Shale and shells	280	700
Shells and redbed	700	750
Sand and shale	750	1000
Shale and redbed	1000	1195
Shale, shells, s rebed	1195	1550
Anhydrite	1550	1590
Shale, redbed and shells	1590	1715
Shale and shells	1715	2087
Lime and shale	2087	2722
Shale	2722	2779
Lime and shale, mostly shale	2779	2950
Lime and shale	2950	3400
Lime	3400	3600
Shale and sand	3600	3625
Red shale	3625	3680 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 30th day of November, 1950.

William Kelly
Notary Public

My commission expires: March 22, 1952.

15-163-02906-00-00
03:50
11-30-50

RECEIVED
STATE CONSERVATION COMMISSION
DEC 1 - 1950
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 25 T 9 R 19W
BOOK PAGE 46 LINE 4