


15-163-60002-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rooks _____ County. Sec. 25 Twp. 9S Rge. _____ (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines _____ SE NW SE
Lease Owner _____ Petroleum, Inc.
Lease Name _____ SCHNEIDER 'D' Well No. 3
Office Address _____ 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____ Dry Hole
Date well completed _____ March 11 1956
Application for plugging filed _____ March 11 1956
Application for plugging approved _____ March 11 1956
Plugging commenced _____ March 11 1956
Plugging completed _____ March 11 1956
Reason for abandonment of well or producing formation _____
Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____ yes

Name of Conservation Agent who supervised plugging of this well _____ Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3614 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 210' and set wooden plug preceded by
1/2 sack hulls and followed by 15 sacks cement displaced
through drill pipe. Mudded up to 40' and set second
wooden plug preceded by 1/2 sack hulls and followed
by 10 sacks cement filling hole to base of well
cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____ Garvey Drilling Company
Address _____ R. R. #2 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Cullen Thomas (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____ Cullen Thomas
_____ 311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1956

My commission expires September 2, 1959

Frances Sloan
Notary Public.

FRANCES SLOAN, Notary Public
My Commission expires Sept. 2, 1959

PLUGGING
FILE SEC-25 T-9 R-1956
BOOK PAGE 46 LINE 6


RECEIVED
STATE CORPORATION COMMISSION
3-23-56
Wichita

WELL LOG

15-163-6000-2-00-00

COMPANY **Petroleum, Inc.**
 FARM **SCHNEIDER 'D'** NO. **3**
 TOTAL DEPTH **3644'**
 COMM. **March 1, 1956** COMP. **March 11, 1956**
 CONTRACTOR **Garvey Drilling Company**

SEC. **25** T. **9S** R. **19W**
 LOC. **SE NW SE**
1650' FEL
1650' FSL
 COUNTY **Rooks**



CASING **8-5/8" @ 218' w/150 sax**

ELEVATION **2197' DF**
2199' RB

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

60	Sand & Clay
218	Clay & Shale
860	Shale & Shells
1510	Sand, Shale & Red Bed
1560	Shale & Shells
1590	Anhydrite
1950	Shale & Shells
3220	Lime & Shale
3337	Lime
3371	Lime & Shale
3624	Lime
3644	Arbuckle
RTD	3644'

Sample Tops

Topoka	3133 (- 934)
Heebner	3341 (-1142)
Toronto	3360 (-1161)
Lansing	3381 (-1182)
Arbuckle	3619 (-1420)

PLUGGING
 FILE SEC 25 T 9 R 19W
 BOOK PAGE 46 LINE 6

State of KANSAS }
 County of SEDWICK } ss:

I, Cullen Thomas of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the SCHNEIDER 'D' #3 well

Cullen Thomas

Subscribed and sworn to before me this 12th day of March 1956

My Commission Expires: September 2, 1959

Frances Sloan
 NOTARY PUBLIC

FRANCES SLOAN, Notary Public
 My Commission expires Sept. 2, 1959