


Give All Information Completely
Make Required Affidavit
Map or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 25 Twp. 9S Rge. 19 ~~(E)~~ XXX (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SW
Lease Owner HEATHMAN & CO., etal
Lease Name BAUMGARTNER Well No. 1
Office Address 509 Orpheum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 3-11- 19 52
Application for plugging filed verbal 3-11- 19 52
Application for plugging approved verbal 3-11- 19 52
Plugging commenced 3-11- 19 52
Plugging completed 3-11- 19 52
Reason for abandonment of well or producing formation ---

If a producing well is abandoned, date of last production --- 19 ---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation none Depth to top --- Bottom --- Total Depth of Well 3719 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>none</u>	<u>---</u>	<u>---</u>	<u>---</u>	<u>8-5/8"</u>	<u>168'</u>	<u>none</u>
					<u>cemented w/120 sacks cement.</u>	<u>---</u>
					<u>No oil string run - Dry and abandoned.</u>	<u>---</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Circulated hole with mud; pushed plug to 160'; cemented w/15 sacks cement; filled w/mud to 40'; set cement plug and cemented w/10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Heathman & Co.
Address 509 Orpheum Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF ~~XXXXX~~ Sedgwick, ss.
H. D. Shreve (employee of owner) ~~owner~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HEATHMAN & CO.
(Signature) By: [Signature]

509 Orpheum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of March, 19 52.


My commission expires June 28, 1952

D. Marjorie Matt
Notary Public.

28-5091-s 8-50-10M

PLUGGING

FILE SEC 25-9-R-190
BOOK PAGE 1 LINE 21



15-163-00466-00-00

WELL LOG
HEATHMAN OIL PRODUCERS
Described as your
Baumgartner #1 Well,
located in Rooks Co.,
Kansas

SE/4 SE/4 SW/4 Sec.25-9S-19W

FROM	TO	FORMATION
0	170	Clay, sand, & shale
170	770	Shale & sand
770	1045	Shale & sand
1045	1289	Sand
1289	1304	Red Bed Shale
1304	1568	Shale & Red Bed
1568	1603	Anhydrite
1603	1852	Red Bed & shale
1852	2050	Shale & shells
2050	2140	Broken lime
2140	2249	Lime & shale
2249	2379	Lime & shale
2453	2615	Shale & lime
2615	2751	Lime & shale
2751	2795	Lime & shale
2795	2880	Shale & lime
2880	3025	Shale
3025	3140	Lime & shale
3140	3153	Shale
3153	3173	Lime
3173	3183	Shale & lime
3183	3250	Lime & shale
3250	3322	Lime & shale
3322	3372	Lime & shale
3372	3412	Lime & shale
3412	3451	Lime & shale
3451	3574	Lime & shale
3574	3604	Lime & shale
3604	3659	Shale & lime
3659	3720	Lime & shale
3720		Total Depth

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

D. Given
D. Given

Subscribed and sworn to before me this 14th day of March, 1952.

My Commission Expires:
October 14, 1953.

Art M. Jump
Notary Public

OWNER: Heathman & Co., et al
Contractor: Lohmann-Johnston Drilling co., Inc.
Surf.Csg.: 168' 8-5/8" cemented w/120 sacks cement
Oil Strang: None run - Dry and abandoned.
Elevation: 2197' Gr; 2199' DF; 2201' KB
Commenced: 2-28-52
Completed: 3-11-52

GEOLOGICAL TOPS	
Anhydrite	1568 (-1633)
Heebner	3362 (-1161)
Toronto	3383 (-1182)
Lansing-KC	3402(-1201)
Base KC	3618(-1417)
Conglomerate	3647(-1446)
Arbuckle	3684(-1483)
T.D.	3719(-1518)

HEATHMAN & CO.

By: *D. Marjorie Mast*

PLUGGING
FILE SEC 25T 9 R 19W
PAGE 1 LINE 21