

15-163-20164-00-00  
Q

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rooks County. Sec. 25 Twp. 9 Rge. 19W (E) (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW SW

Lease Owner Three G Oil, Inc.

Lease Name Baumgartner Well No. 1

Office Address 1101 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-23 19 68

Application for plugging filed 12-23 19 68

Application for plugging approved 12-23 19 68


Plugging commenced 12-23 19 68

Plugging completed 12-23 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 3672 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	220'	-

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug @ 720' & pump 70 sacks cement  
Set plug @ 210' & pump 20 sacks cement  
Set plug @ 40' & pump 10 sacks cement  
Cemented by Sun Cementing with 50-50 pozmix, 6% jel

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to

Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

300 Schweiter Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of December, 19 68



Martha Gage  
Notary Public.

My commission expires December 14, 1969

15-163-20164-00-00

DRILLERS LOG

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1968  
CONSERVATION DIVISION  
Wichita, Kansas

#1 BAUMGARTNER  
NW NW SW Section 25-9S-19W  
Rooks County, Kansas

OPERATOR: Three G Oil, Inc.  
1101 Wichita Plaza  
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.  
300 Schweiter Building  
Wichita, Kansas

COMMENCED: December 15, 1968

COMPLETED: December 23, 1968

CASING RECORD: 8-5/8" @ 220' w/150 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	50	Clay
50	75	Sand
75	220	Shale and shells
220	350	Blue shale & clay
350	1440	Shale, sand, shells
1440	1552	Red Bed
1552	1589	Anhydrite
1589	1768	Shale & shells
1768	2390	Lime & shale streaks
2390	2739	Lime & shale
2739	2865	Broken lime
2865	3200	Shale & lime
3200	3670	Lime
		Rotary Total Depth

STATE OF KANSAS )  
                          ) ss  
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.

  
Don Gardner

Subscribed and sworn to before me this 30th day of December, 1968.

My commission expires:  
December 14, 1969

  
Notary Public

