

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE-SE-NE, Sec. 30, T 11 S, R 14 W1/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22, 160-00-00

2310 feet from (N)S section line

330 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name STRECHER Well # 2

Operator: RAINS & WILLIAMSON OIL CO. INC.
Name & Address: 435 PAGE COURT
220 WEST DOUGLAS
WICHITA, KANSAS
67202

County RUSSELL

Well Total Depth 3540 feet \$115.05

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor RAINS & WILLIAMSON OIL CO. License Number 5146

Address 435 PAGE COURT, 220 WEST DOUGLAS, WICHITA, MO. 67202

Company to plug at: Hour: 1:30 PM Day: 13th Month: SEPT. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO LARRY HENDERLEITER

(company name) RAINS & WILLIAMSON OIL CO (phone) 316-265-9686

were: 8 5/8" - 293 FT SB. CUL. #160 SK SUN. SET. (BY SUN CNT.)

ORDER 200 SK 50/50 Formix 4% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM-TURN HOLE OVER, MUD BETWEEN ALL PLUG.

ARBUCKLE @ 3507 FT, ELV 1811 FT ANHY. 905 FT

Signed *Marion Schmidt*
(TECHNICIAN) 001C

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 PM Day: 13th Month: SEPT Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 200 SK 50/50 Formix 4% GEL, 3% CA-CL, AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM, TURNED HOLE OVER, MUD BETWEEN ALL PLUG.

1st PLUG @ 3485 FT #120 SK CNT., 2nd PLUG @ 930 FT #120 SK CNT.

3rd PLUG @ 660 FT #80 SK CNT., 4th PLUG @ 300 FT #50 SK CNT.

5th PLUG SOLID BRIDGE HULL'S-PLUG @ 40 FT #10 SK CNT, 10th BIT HOLE (AIR)

Remarks: (CEMENTED BY ALLIED CNT.)

I hereby certify that the above plugging instructions were given as herein stated and that I (/ did not) observe this plugging.

Signed *Marion Schmidt*
(TECHNICIAN) 001C ✓

INVOICED RECEIVED
STATE CORPORATION COMMISSION
DATE 9-28-83 SEP 19 1983
INV. NO. 5582-L
CONSERVATION DIVISION
Wichita, Kansas