

6070285

API NUMBER 15-167-22, 537-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE-NW-NW, SEC. 15, T. 11 S, R. 14 W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146 Lease Name BARTLETT Well # 1  
Operator: RAINS AND WILLIAMSON OIL CO. County RUSSELL CO. 117.71  
Name & Address 435 PAGE COURT, 220 WEST DOUG. Well Total Depth 3363 feet  
WICHITA, KANS. Conductor Pipe: Size 0 feet  
67202 Surface Casing: Size 8 5/8 feet 301 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated TABLE 62

Plugging Contractor RAINS AND WILLIAMSON DRIG. CO. License Number 3146

Address 435 PAGE COURT, 220 WEST DOUGLAS, WICHITA, KANS. 67202

Company to plug at: Hour: 8:00 PM Day: 9<sup>th</sup> Month: JAN Year: 19 85

Plugging proposal received from LARRY HENDERLEITER

(company name) RAINS AND WILLIAMSON DRIG (phone) 316-265-9686

were: ORDER 180<sup>SK</sup> 50/50 PERMIX GEL-CA-CL-1 4 1/2" 3 1/2" SK CELLO FLARE AND 8 5/8" PING.

SPOT WITH DRILL STEM, RECONDITION HOLE (50 WTS) HEAVY MUD BETWEEN ALL PLUGS  
DIDNT OPEN ARBUCKLE (CONGLOMERATE) NO CIRCULATION PROBLEMS, MUD WEIGHT 10.3  
WELL  
VS. 50, WATERLOSS 12.8, CHLORIDES 50, ELV 1700 ANH. 823

Plugging Proposal Received by MARION SCHMIDT  
BOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:15 PM Day: 9<sup>th</sup> Month: JAN Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 180<sup>SK</sup> 50/50 PERMIX GEL-CA-CL-1 4 1/2" 3 1/2" SK CELLO FLARE AND 8 5/8" PING.

SPOTTED WITH DRILL STEM - RECONDITIONED HOLE - HEAVY MUD BETWEEN ALL PLUGS.  
1<sup>st</sup> PUG @ 840 ETM/30<sup>SK</sup> INT - 2<sup>nd</sup> PUG @ 570 ETM/80<sup>SK</sup> INT - 1<sup>st</sup> SK CELLO FLARE  
3<sup>rd</sup> PUG @ 240 ETM/50<sup>SK</sup> INT, 4<sup>th</sup> PUG SOLID BRIDGE HULL'S - PUG @ 40 ETM/10<sup>SK</sup> INT.  
10<sup>th</sup> RAT HOLE (CIRCULATE) CEMENTED BY ALLIED OIL.

RECEIVED  
STATE CORPORATION COMMISSION  
1-17-1985  
JAN 17 1985

Remarks: additional description is necessary, use BACK of this for CONSERVATION DIVISION  
Wichita, Kansas  
DATE 1-31-85 (did not) observe this plugging.

Signed MARION SCHMIDT 2  
BOIC (TECHNICIAN) 1-16-84  
MOS

INV NO. 6760