

12-6-87

6 020429

API NUMBER 15- 167-22-795-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SE, SEC. 18, T 11 S, R 14 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Operator: Oil Producers Inc. of Ks.
Name &

Address Box 8647

Wichita, Ks. 67208

Lease Name Chrysler-Roda Well # 1

County Russell 106.28

Well Total Depth 3270 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 233

Abandoned Oil Well Gas Well Input Well SWD Well U&A X

Other well as hereinafter indicated

Plugging Contractor Western Ks. Drilling License Number

Address Jim Manley

Company to plug at: Hour: Day: 5 Month: Dec Year: 19 87

Plugging proposal received from Jim Manley

(company name) W. K. D. (phone)

were: Order 170 sks 60/40 Poz 6% Gel 3% Ca Cl 1 sk Flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gil Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:45 AM Day: 6 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT Cir Heavy Mud

STATE CORPORATION COMMISSION

1st plug at 950' w/25 sks

2nd plug at 550' w/80 sks and 1 sks F.C.

3rd plug at 230' w/40 sks

4th plug at 40' w/10 sks/wiper

15 sks in rat hole.

RECEIVED
1-18-1988
JAN 18 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cemented by Halliburton (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-30-88

INV. NO. 19611

Signed Gilbert Balthazor (TECHNICIAN)