

6 030727

API NUMBER 15-167-22,741-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SUNWNE SEC. 19, T. 11 S., R. 14 (W) 2

4290 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name CHRISLER-RODA Well # 1

Operator: RAINS & WILLIAMSON OIL CO INC
Name &

County RUSSELL 11213

Address 435 PAGE COURT 220 WEST DUG,

Well Total Depth 3450 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 7/8 feet 262

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor SAME AS OPERATOR License Number 5146

Address _____

Company to plug at: Hour: PM Day: 24 Month: 4 Year: 19 86

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 8 7/8 @ 262 w/ 180 SX. CIRC. HOLE WITH HEAVY MUD MAINTAIN
FLUID @ SURFACE SPOT CNT. PLUGS W/ D.P. DISPLACE W/ MUD
ORDER 155 SX. 60/40 PZ C'GEL 3% @ B J TITAN CNT. CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5: PM Day: 24 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT SPOT D.P. @ 925' DISPLACE 90 SX. CNT. MIX.
LAYDOWN D.P. TO 300' DISPLACE 40 SX. CNT. MIX. LAYDOWN D.P.
ADJUST MUD LEVEL @ 40' E LOAD HOLE WITH 10 SX CNT. MIX TO
BASE OF CELLAR DISPLACE 15 SX. IN RATHOLE. PLUG COMP'

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1986

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE: MAY 19 1986

NO. 13879

Signed Carl Goodrow
(TECHNICIAN)

4-24 MAY 28 1986