

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20284-00-05 ⁰¹ *Kc aff 12-5-08*
Spot: SWSWSW Sec/Twnshp/Rge: 34-5S-23W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: WYRILL C Well #: 1
County: NORTON Total Vertical Depth: 3980 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3777	0	175 SX
SURF	8.625	335	0	185 SX

129.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2008 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perforate at 2050' and 1270'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2008 12:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2300' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1200' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls - circulated cement to surface.
Pulled all tubing - topped off 4 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.
Hooked onto backside - pumped 15 sxs 60/40 pozmix - 4% gel.
150# pressure before blowing out.

Perfs:

Top	Bot	Thru	Comments
3706	3710		
3678	3684		

INVOICED
DATE 09/16/08
INV. NO. 2009060382

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 22 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #31583.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

AUG 21 2008

10557 AS
 1625 2100
 161000

REPLACEMENT CARD

F & M OIL COMPANY, INC.
 422 UNION CENTER
 WICHITA, KS 67202

#1 "C" WYRILL; P


34-5-23W
 SW SW SW

CONTR UNION DRILLING CO.

CTY NORTON

GEOL

FIELD WC(NORHAM DISC)



ELV 2370 KB SPD 4/12/83 CARD ISSUED 6/16/83

IP P 100 BOPD, NW
 LKC 3678-3710 OA

LOG	Tops	Depth/Datum
ANH	2000+	370
B/ANH	2030+	340
TOP	3322-	952
HEEB	3520-	1150
TOR	3543-	1173
LANS	3559-	1189
BKC	3749-	1379
CONG	3896-	1526
ARB	3949-	1579
PBTD	3745-	1375
LTD	3977-	1607
RTD	3980-	1610

API 15-137-20,284

8 5/8 " 335 / 185SX, 4 1/2 " 3777 / 175SX

DST (1) 3500-60 (SHAW) / 30-45-30-45, SB THRU-OUT, 280' GIP, REC 540' HVY GSY OCM, 450' OIL SPKD MW, TOTAL FL (GRIND OUT: 201' OIL, 108' M, 681' WTR), SIP 1246-1225#, FP 106-308 / 361-489#, BHT 103°

DST (2) 3561-72 (LKC) / 30-45-30-45, GB INCRG TO SB BOTH OP'S, 490' GIP, REC 210' CL GSY OIL (BTM 20' SL MDY, NW - GR 28°), SIP 1215-1025#, FP 42-53 / 85-95#

DST (3) 3583-3600 (LKC) / 30-45-30-45, SB THRU-OUT, REC 670' SL MDY SW (CHL 50,000 PPM), SIP 1278-1278#, FP 33-170 / 238-329#, BHT 105°

DST (4) 3603-30 (LKC) / 30-45-30-45, SB THRU-OUT, 920' GIP, REC 1300' CL GSY OIL (GR 36°), SIP 1299-1299#, FP 95-276 / 320-457#

INFO RELEASED: 3/7/85 - WAS OIL WELL - TIGHT HOLE
 (over)