

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

## TECHNICIAN'S PLUGGING REPORT

Operator License # 33344Operator: Quest Cherokee, LLCName & 211 W. 14th 210 PARK Ave, Ste 2750Address Chanute, Kansas 66720 73102AB oil well XXXXXX Gas Well \_\_\_\_\_

SWD Well/ Input Well \_\_\_\_\_

D &amp; A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Quest Cherokee, LLCLic. # 33344Address: 211 W. 14th, Chanute, Kansas 66720Company to plug at: Hour: \_\_\_\_\_ Day: 31 Month: 7 2007Plugging proposal received from: Jerry LesterCompany Name: Quest Cherokee, LLC Phone: 620-432-3519Were: Clean old well bore to TD and fill from btm to top with portland cement.Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXOperations Completed: Hour: \_\_\_\_\_ Day: 1 Month: 8 2007Actual Plugging Report: 7-25-07: 2.375" tubing with a drill bit was lowered to 30' The well was then drilled to 881' at which point the bit plugged.7-26-08: The bit was pulled and cleaned. The bit was then lowered down hole and drilled to 910', then pulled.7-30-08: A 1" cement string was lowered to 910' and the well washed to 962' where TD was encountered.7-31-08: A 1" cement string was lowered to 962' and cement pumped from btm to top thru 1" cement string.Used all the cement available - will finish tomorrow.8-1-08: Cement was tagged at 85'. The well was then filled from 85' to surface thru cement string. A totalof 215 sacks of portland cement were used to plug well.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

RECEIVED

KANSAS CORPORATION COMMISSION

Signed: \_\_\_\_\_

TECHNICIAN

INVOICED

OCT 09 2008

DATE

11-26-08

INV. NO.

2009060783

CONSERVATION DIVISION  
WICHITA, KS