

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22,193-00-00

NE 1/4 SEC. 25, T. 11 S., R. 15 W. 1/2

1650 FEET FROM N 1/8 SECTION LINE

1980⁸⁵⁰ FEET FROM 1/4 E. SECTION LINE ^{E3} 12/14/08

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6194

LEASE NAME Morrell WELL # 1

OPERATOR: EAP Development
NAME & ADDRESS C/O Lewis Eubert
Paradise, Ks. 67658

COUNTY Russell

WELL TOTAL DEPTH 3550 \$115.38 FEET

CONDUCTOR PIPE: SIZE - FEET -

SURFACE CASING: SIZE 8 5/8 FEET 245

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Emphasis Oil Operations LICENSE NUMBER 8241

ADDRESS P.O. Box 506 Russell, Kansas 67665-0506

COMPANY TO PLUG AT: HOUR: 9:30 A.M. DAY: 26 MONTH: August YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Ron Burton

(COMPANY NAME) Emphasis Oil Operations (PHONE) 913-483-3518

WERE: Order 180 sh. 50/50 posmid, 4% gel, 3% cal. cl.
+ 8 5/8" wire plug, spot w/ drill pipe w/ heavy mud
between all plugs.

PLUGGING PROPOSAL RECEIVED BY Edwin A. Schumacher
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 9:30 AM DAY: 26 MONTH: August YEAR: 19 83

ACTUAL PLUGGING REPORT 1st plug 3550' w/ 20 sh. cmt.

2nd plug 985' w/ 20 sh. cmt.

3rd plug 510' w/ 80 sh. cmt.

4th plug 290' w/ 40 sh. cmt.

5th plug 40' solid bridge - 1 sh. hulla 10 sh. cmt.

10 sh. in rat. hole

REMARKS: Elevation - 1880'

Anhydrite - 976' (Allied Cementing)

Arbuckle - yes

I (DID / DID NOT) OBSERVE THIS PLUGGING.

INVOICED

DATE 10-4-83

INV. NO. 5634-W

RECEIVED
STATE CORPORATION COMMISSION
9-26-1983
SEP 26 1983

CONSERVATION DIVISION
Wichita, Kansas

SIGNED Edwin A. Schumacher
(TECHNICIAN)

FORM CP-2/3
" REV. 6-83