

6-100466

11-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,604-00-00

W2 SW NW /4 SEC. 28, 10 S, 32 W
3300 feet from S section line
4950 feet from E section line

Operator license# 5856 Lease Peck well # 1

Operator: The Dane G. Hansen Trust County Thomas

Address: P.O. Box 187 Well total depth 4690 feet
Logan, Kansas 67646 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 338 feet

152.43

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Chief Drilling, Inc. License# 5886

Address: _____

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Harold Dinkel

Company: Chief Drilling, Inc. phone: _____

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

- 1st plug @ 2580 feet with 25 sacks Rat hole: 15 sacks
- 2nd plug @ 1765 feet " 100 " Mousehole: 10 sacks
- 3rd plug @ 380 feet " 40 "
- 4th plug @ 40 feet " Wiper plug & 10 sx.

5th plug @ _____ feet

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:30 pm, Day: 21, Month: November, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED

STATE CORPORATION COMMISSION

12-11-1992
DEC 11 1992

Remarks: Elevation: 3067 GL, Anhydrite depth: 2581 - feet

Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: NO

Plugged through drill pipe: YES

Did NOT penetrate Arbuckle, cemented by Allied Cement

I did [] / did not [X] observe the plugging.

David K. Wann P.I.R.T. II (agent)

INVOICED
DATE 1-4-93
INV. NO. 37078