

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20231-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1969
CONSERVATION DIVISION
Wichita, Kansas
06-06-1969

Operator's Full Name Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name Faulkner Well No. 1

Location CNE-SE Sec. 34 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3822'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:30 AM Day 4 Month 6 Year 1969

The Above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 940' and displaced 100 Sx. cement thru
DP from 940' to 615'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/6/69
INV. NO. 9906-W

Signed: W. L. Nichols
Well Plugging Supervisor