

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-065-02953-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

W

FILE NO. _____

LOCATION ^{SW} NW-NE-

SEC. 34 TWP. 10 RGE. 22

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-2 Lease Webster

Operator Wood-River-Oil Co. Address Wichita-Kansas

Field 335-W. Lewis County Graham

Total Depth 3991 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" - 1800ft Cemented from top to bottom
5 1/2" casing set at 3969ft & cemented with 200 sacks cement
Well had been plugged back to 3610ft & prepared three
Bridges & Plug Put in at 3580ft & 10 sacks cement
with Bruce Bailey - 5 1/2" casing shot off at 2950ft & pulled
Hole filled with heavy mud to 1800ft - & three Plug set
& 10 sacks cement - Hole then filled with mud to 200ft

Plug & 10 sacks cement at 200ft
then mud to within 20ft of
the surface & 10 sacks of cement
2950ft of 5 1/2" casing removed

C. D. Stough
District Conservation Agent

Date 7-24-47

PLUGGING
FILE SEC 34 T 10 R 22
BOOK PAGE 122 LINE 23

