

15-065-02952-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 137-14

LOCATION SW NE NE

SEC. 34 TWP. 10 RGE. 22

Dry Hole          Abandoned Oil Well X Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. B-1 Lease Webster

Operator Woodriver Oil & Refg Address 321 Douglas West Wichita,

Field          County Trego

Total Depth 3999 Feet.

Plugging Contractor Bert Self Pipe Pulling

Plugging Contractor's License No. 48

Address         

(Describe briefly the manner in which the well was plugged)

13" at 282' circulated with cement - 8 5/8" at 1817' - 5 1/2" at  
3978' with 150 sax cement behind.

Filled with chat to 3970', set 4 sax cement with dump bailer,  
pulled 2600' 5 1/2", pumped hole full mud ( 30 sax mud and 15 sax hulls)  
pulled 1203' 8 5/8", mud to 280', set rock and 30 sax cement,  
mud to 25', set rock and 15 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 34 T 10 R 22  
BOOK PAGE 137 LINE 14

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1954  
02-18-1954  
CONSERVATION DIVISION  
Wichita, Kansas

*Edna J. [Signature]*  
District Conservation Agent  
Date 2-12-54