

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20300-00-00

01-12-1970
RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Matthews Well No. 1

Location NW-NW-NW Sec. 33 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 3:45 PM Day 9 Month 1 Year 1970

The above well was plugged as follows:

199'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru
DP from 900' to 575'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 1/12/70
INV. NO. 1235-W