

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1964
09-09-1964
CONSERVATION DIVISION
Wichita, Kansas

15-065-01063-00-00

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Klenk Well No. 1

Location NE-SW-NW Sec. 3 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3975

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 8:00AM Day 7 Month 9 Year 1964

The Above well was plugged as follows:

189'--8 5/8" Surface pipe, cement circulated with 145 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx. cement thru DP/

Heavy mud to 180', set plug with 1/4 sack hulls and displaced 20 Sx. cement thru DP.

Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 9/9/64

INV. NO. 9489-W