

15-045-03309-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 76-38
LOCATION NE NE NE
SEC. 3 TWP. 10 RGE. 23

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Klenk

Operator Birmingham-Bartlett Address Wichita, Kans

Field _____ County Graham

Total Depth 4245 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 163' circulated with cement - 5 1/2" at 4208' with

125 sax cement behind - perforated at 3897' - set plugs at 3850'

set 4 sax cement with dump bailer at 3850', pulled 1500',

5 1/2", hole filled with mud to 160', set rock and 15 sax cement,

mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1956
09-21-1956
CONSERVATION DIVISION
Wichita, Kansas

Edward J. Kelly
District Conservation Agent

Date 7-18-56

PLUGGING
FILE SEC. 3 T. 10 R. 23w
BOOK PAGE 76 LINE 38