

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 1962  
03-07-1962  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-065-03310-00-00

File No. \_\_\_\_\_ County: Graham

Location: NE NE SE Sec. 3 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 23

Name of Field: \_\_\_\_\_ Total Depth: 4310

I have this date completed supervision of plugging of:

Lease Name: Klenke Well No. 1

Operator's Full Name: Quality Supply Co

Complete Address: 701 Union Natl Bldg Wichita, Kansas

Plugging Contractor R & D Casing Pulling

Address: Hutchinson, Kansas License No. 236

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4:30 PM Day 4 Month 3 Year 62

The above well was plugged as follows:

13" 195' circulated with cement - 7" 4308' with 150 sax cement - perf 3925 & 3710' - filled with sand to 3690', set 5 sax cement with dump bailer.

Pulled 2500' 7" to 550', circulated hole with heavy gel mud - displaced 25 sax cement through 7" at 550', heavy mud to 180', displaced 35 sax cement through 7" at 180', heavy mud to 25' - cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: Edon Tully  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED  
DATE 3/16/62  
INV. NO. 4638-W