

10  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 28 1964  
12-28-1964  
CONSERVATION DIVISION  
Wichita, Kansas

15-065-03058-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Imperial Oil of Kansas, Incorporated,  
Complete Address: 2318 Washington, Great Bend, Kansas.  
Lease Name Rice Well No. 1  
Location NE-SW-SE Sec. 4 Twp. 10 Rge. (E) (W) 23  
County Graham Total Depth 4241  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Southwest Casing Pulling Company, Incorporated,  
Address: Box #364, Great Bend, Kansas. License No. 399  
Operation Completed: Hour 4:00PM Day 21 Month 12 Year 1964

The Above well was plugged as follows:

190' -- 8 5/8" Surface pipe, cement circulated with 150 Sx.  
4240' -- 5 1/2" Production casing cemented with 125 Sx. Well plugged back to  
4165'. Top perforations from 3822' to 3826'.  
Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled  
5 1/2" to 600' and circulated heavy gel mud. (Used 25 Sx. gel). Pulled 5 1/2"  
to 540' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 180' and  
displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" set bridge @ 30' and 10 Sx.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 12/28/64  
INV. NO. 411-W

Signed: W. L. Nichols  
Well Plugging Supervisor