

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1970
CONSERVATION DIVISION
Wichita, Kansas
10-12-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20276-00-00

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Shaw Well No. 1

Location 100' NE of CNE-NW Sec. 5 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 4010'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 12:00 M Day 7 Month 10 Year 1970

The above well was plugged as follows:

158+-8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru
DP from 1125' to 800'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from
185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dreiling
Well Plugging Supervisor

DATE 10-12-70
INV. NO. 2666-4