

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1974
05-22-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20675-00-00

Operator's Full Name Murfin Drilling Company.
Complete Address 617 Union Center, Wichita, Kansas.
Lease Name Shaw-Clifford Well No. 1
Location SE-NW-SW Sec. 5 Twp. 10 Rge. (E) (W) 23
County Graham Total Depth 4010'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 10:30 PM Day 18 Month 5 Year 1974

The above well was plugged as follows:

151'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 110 Cu. Ft. cement
thru DP from 1100' to 775'. Pulled DP to 155' and displaced 30 Cu. Ft. cement thru
DP from 155' to 80'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Daniels
Well Plugging Supervisor

INVOICED

DATE 5/23/74

INV. NO. 9184-W