



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1974
03-07-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20500-00-00

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: C. Dreiling Well No. 2

Location: NE-NE-NW Sec. 8 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4085' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

199'--8.5/8" Surface casing, cement circulated with 165 Sx.
4072'--4 1/2" Production casing cemented on bottom with 200 Sx. Top perforations from 3996' to 4002'.

Push plug to 3900', sand well back to 3850' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent