

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-179-20399-00-00

RECEIVED  
STATE CORPORATION COMMISSION

MAY 28 1975  
05-28-1975  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Drieling Oil Inc. has this date requested permission to plug the following described well:

Mr. Bill Draper guarantees payment of the plugging fee.

Operator's full Name: Drieling Oil Inc.

Complete Address: RT. 2 - Victoria Kansas.

Lease Name: Tilton Well No. #1

Location: W/2 - NW - SE Sec. 30 Twp. 10 Rge. 26 (E) (W) W

County: Sheridan Total Depth 3855 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Bill Draper was instructed to plug the well as follows:

Pump down drill stem.  
70 sx cem. 50/50 Poz mix 6% Gel @ 1100'  
20 " " " " " " @ 190'  
Bridge - 1sx Hulls & Plug 70 40'  
10 sx cem 50/50 Poz mix 6% Gel on the Top.

Very truly yours,

Gulley Balchman  
Conservation Division Agent