



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20150-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas
08-31-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russ Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Tilton Well No. 1

Location: CNE-SW Sec. 30 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 4370' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

177'--8 5/8" Surface casing, cement circulated.

4039'--4 1/2" Production casing cemented on bottom with 200 Sx. Top of cement @ 3460' (Temp. Survey). Top perforations from 3811' to 3814'.

Measure bottom of well, sand back above top perforations and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 Sacks hulls, 30 sacks gel and 135 Sx. cement staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent