



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1969
CONSERVATION DIVISION
Wichita, Kansas
07-18-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

15-179-20220-00-00

Mr. Vernon Zorn of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Zorn guarantees payment of the plugging fee.

Operator's full Name: Dreiling & Hiko Bell Mining and Oil Co.

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Miller Well No. #1

Location: SE-NW Sec. 30 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 4050' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zorn was instructed to plug the well as follows:

188'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1050'

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent