

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 28 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 01-28-1969

15-179-20176-00-00

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Dreiling & Hiko Bell Mining & Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Tilton Well No. 2

Location: SE-SW Sec. 30 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 3995' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

178'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1240' and displace 100 Sx.  
cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*W. L. Zschab*

Conservation Division Agent