



15-065-~~02776~~-00-00

02976 1000 eps  
~~02776~~-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas

1/11/71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrel Kelso of Knight Csg. Pulling Co., Inc., has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: J. K. Fortner

Complete Address: Box #97, #111wood, Kansas.

Lease Name: Bethell Well No. 21 <sup>WHM</sup> <sup>KCC</sup> 10/13/05

Location: NW-SE-NE Sec. 17 Twp. 8 Rge. (E)(W)23

County: Graham Total Depth 3622' Oil Well 2

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

162'--8 5/8" Surface casing, cement circulated with 120 Sx.  
3620'--5 1/2" Production casing cemented on bottom with 100 Sx. No Plug Back, Top perforations @3354'.

Sand back to 3300' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx. cement, staged.

Very truly yours,

A. L. Dehler  
Conservation Division Agent