



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1973  
04-20-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20207-00-01

Dear Sir:

Mr. Gilbert Scheck of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Scheck guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Zerr Well No. 2

Location: CSW-SW Sec. 22 Twp. 10 Rge. (E)(W) 27

County: Sheridan Total Depth 4030' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Scheck was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 160 Sx. (WASHDOWN).  
4028'--4 1/2" casing cemented on bottom with 225 Sx. Top of perforations @ 3796'.

Sand well back to 3500' and set # Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent