

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-179-20086-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
04-08-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Heier Well No. 1

Location: CNW-NE Sec. 1 Twp. 10 Rge. (E)(W) 29

County Sheridan Total Depth 4235 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cooke was instructed to plug the well as follows:

226'--7 5/8" OD Surface pipe, cement circulated with 125 Sx. (6 3/4" Hole).  
Top of Dakota section @ 1220'

Circulate hole with heavy mud. Pull DP to 1450' and displace 80 Sx.  
cement thru DP. Pull DP to 240' and displace 15 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

Conservation Division Agent