



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-179-20235-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1969
CONSERVATION DIVISION
Wichita, Kansas
10-14-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Burkhart of Sage Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Burkhart guarantees payment of the plugging fee.

Operator's full Name: Braden Drilling, Incorporated.

Complete Address: 1620 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Blank Well No. 2

Location: CSW-NE Sec. 15 Twp. 10 Rge. (E)(W) 29

County: Sheridan Total Depth 11200 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burkhart was instructed to plug the well as follows:

289'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent