



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
01-15-1970

15-179-20148-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Beakey of Forbes Casing Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Beakey guarantees payment of the plugging fee.

Operator's full Name: Braden Drilling, Incorporated,

Complete Address: 1620 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Blank Well No. 1

Location: NE-NE Sec. 15 Twp. 10 Rge. (E)(W) 29

County: Sheridan Total Depth 4238' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Beakey was instructed to plug the well as follows:

288'--8 5/8" Surface casing, cement circulated.  
4230'--5 1/2" Production casing cemented on bottom with a Temperature Survey showing top of cement @ 3516'. Well plugged back to 3990' Top perforations @ 3949'.

Sand well back to 3525' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 130 Sx. cement staged.

Very truly yours,

*A. G. Nichols*  
Conservation Division Agent