

KCC OIL/GAS REGULATORY OFFICE

Date 10/30/08

- New Situation
- Response to Request
- Follow-up

Operator license # 32158

Operator H & B Petroleum Corp

Address P.O. Box 277

Location SESESW Sec 18, T 22S, R 33W

Ellinwood, Ks 67526

Lease Garden City Well # 2-18

Operator phone number 620 564-3002

County Finney

Reason for Investigation: Alternate II Cementing API # 15-055-22010-0000

8 3/8" x 442', 5 1/2" x 4941 w/ 2055x. Port collar x 2017

Problem: Csg was run 8-30-08. (2 months ago)

Person(s) Contacted: _____

Findings: Allied pumped 1505x 60/40 Pz 8% gel thru port collar
x 2017' w/ no blow on surface. Close port collar.
Reverse out cement. Log Tech of Kansas perf 4 holes
x 1120'. Run log & packer. Allied pumped 1955x
60/40 Pz 8% gel x 1005x CIA thru ports. Full circulation.
Circulated 755x to the pit.

photos taken: _____

Action/Recommendations: Alternate II Only complete

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 12 2008

CONSERVATION DIVISION
WICHITA, KS

- Lease Inspection
- Complaint
- Field Report

By Ken Sepite

PIRT II

- RBDMS
- TA program
- KGS
- T-1 database
- District files
- Courthouse

Retain 1 copy Joint District Office
Send one copy Conservation Division

