

KCC OIL/GAS REGULATORY OFFICE

Date 11/3/08

- New Situation
- Response to Request
- Follow-up

Operator license # 32825

Operator Pioneer Exploration

Address 15603 Kuykendahl

Location NE NE NE Sec 19, T 22 S, R 33 W

Suite 200
Houston, Tx 77090

Lease Coarden City B Well # 3-19

Operator phone number 281 893-9400

County Finney

API 15-055-21976-0000

Reason for Investigation: Alternate II Cementing

8 5/8" 337'; 4 1/2" 4949 w/ 400sx. DV tool 2682

Problem: Cement did not circulate to surface w/ 750 sx
on primary top stage cementing job.

Person(s) Contacted: _____

Findings: _____

Log Tech ran CBL. Found TOC % 1472' Part 4 holes % 1100'
Allied pumped 140 sx 60/40 Pa 8% gel followed by
100sx CIA. Evul returns. Circ 1103x to the pit.

photos taken: _____

Action/Recommendations: Alternate II Comtg Complete

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 12 2008

CONSERVATION DIVISION
WICHITA, KS

By Ken Jehlik

P I R T II

- Lease Inspection
- Complaint
- Field Report

- RBDMS
- KGS
- District files
- TA program
- T-1 database
- Courthouse

Retain 1 copy Joint District Office,
send one copy Conservation Division

