

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15-151-19031-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 05/02/1951

Well Operator: Iuka-Carmi Development, LLC KCC License #: 31739
(Owner / Company Name) (Operator's)

Address: PO Box 907 City: Pratt

State: Kansas Zip Code: 67124 Contact Phone: (620) 672-9571 Ext 5

Lease: Helmke (ICHU 15) Well #: B-6 Sec. 7 Twp. 27S S. R. 12 East West

C - E/2 - NW - NE Spot Location / QQQQ County: Pratt

660 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 425' Cemented with: 250 Sacks

Production Casing Size: 5 1/2" Set at: 4233 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 2723' to 3070' BP @ 3136'

Elevation: 1885 (G.L. / K.B.) T.D.: 4262 P.B.T.D.: 3136 Anhydrite Depth: unknown
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): sand perfs or set CIBP above perfs with 2 sacks of cement, free point, pull casing

**RECEIVED
KANSAS CORPORATION COMMISSION**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

OCT 17 2008

If not explain why? we do not have records
**CONSERVATION DIVISION
WICHITA, KS**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Gareld Insee

Phone: (620) 770-0995 (cell phone)

Address: PO Box 907 City / State: Pratt, KS 67124

Plugging Contractor: Pratt Well Service, Inc. KCC License #: 5893
(Company Name) (Contractor's)

Address: PO Box 907 Pratt, Kansas 67124 Phone: (620) 672-9571 Ext 5

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/16/08 Authorized Operator / Agent: Keith Chiles
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Dist 1
PRT*

GETTY OIL COMPANY
2705 VINE, UNIT 4
HAYS, KS 67601


"OWWO"
#6 "B" HELMKE

7-27-12W
C E/2 NW NE

CONTR BASYE WELL SERVICE CTY PRATT

GEOL _____ FIELD IUKA

ELV 1884 KBSPD 2/24/83 CARD ISSUED 1/26/84 IP FLO 80 MCFGPD
1882 GL WAB 2723-2724



API NOT ASSIGNED

SMP	Tops	Depth/Datum
HEEB SH		3450-1566
DOUG SD		3535-1651
BR LM		3678-1794
LANS		3700-1816
MISS LM		4083-2199
KIND SH		4107-2223
VIOLA		4124-2240
SIMP SH		4204-2320
SIMP DOL		4223-2339
SIMP SD		4233-2349
PBTD		2765- 881
RTD		4268-2384

OLD INFO: OPERATOR WAS SKELLY OIL COMPANY, #6 "B" HELMKE, SPD 5/12/51, SET 8 5/8 " 425 / 250 SX, 5 1/2 " 4233 / 200 SX, COMP. AS P 116 BO & 20 BWP, (CARD ISSUED 6/15/51), CONTR: UNKNOWN
NO DST'S

NEW INFO: FR 1/24/84, RE-ENTERED 2/24/83, WSH DWN, PROD CSG IN HOLE, MICT - CO, PF (SIMP) 4233-4262, FRAC 1500 GAL KEROSENE & 1400# SD, SWB LD, NS, SET BP (DEPTH NA), PF 3 / 2895, SWB LD, NS, PF 2794-2798, W / 2 SPF, AC 1300 G, SWB LD, NS, PF 3066-3070, W / 2 SPF, SWB LD, NS, PF 2552-2553, W / 2 SPF, AC 200 G, SWB LD, NS, PLUGGED OFF ABOVE PFS, PF (WAB) 2723-2724, W / 3 SPF, SWB LD, KOF, SI, FLO 80 MCFGPD, 10-28-83

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

IUKA-CARMI DEVELOPMENT LLC
PO BOX 847
PRATT, KS 67124-0847

November 07, 2008

Re: HELMKE #B-6
API 15-151-19031-00-00
7-27S-12W, 660 FNL 990 FWL
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after May 6, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888