

15-179-20843-00-00

KCC
FORM CP-1
Rev. 6/4/84

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-179-20,843 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Energy Exploration, Inc. OPERATORS LICENSE NO. 5063

ADDRESS 1002 So. Broadway, Wichita, KS 67202 PHONE # (316) 267-7336

LEASE (FARM) TROUTMAN WELL NO. 1 WELL LOCATION SE NW SE COUNTY Sheridan

SEC. 9 TWP. 10S RGE. 26W (E) or (W) (W) TOTAL DEPTH 4150' PLUG BACK TO

Check One:

OIL WELL GAS WELL D & A XX SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 339.50' CEMENTED WITH 265 SACKS

CASING SIZE - - SET AT - - CEMENTED WITH - - SACKS

PERFORATED AT - - - -

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 2260' w/30 sx. 2nd plug @ 1340'
w/100 sx. 1 sx. Celoflake. 3rd plug @ 340' w/50 sx. 4th plug @ .40' Sol. Bridge w/10 sx.
10 sx./Rathole. 60-40 pozmix, 6% gel, 3% c.c.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? NO
(If not, explain)

Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3:45 p.m., 9/14/85.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. '55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Craig, Sr. (Toolpusher) PHONE # (913) 674-2876 RECEIVED

ADDRESS Box 297, Hill City, KS 67642 STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422 OCT 18 1985

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841 CONSERVATION DIVISION
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack L. Partridge
(Operator or Agent)

Jack L. Partridge, Vice President
October 1, 1985

DATE: October 1, 1985