

15-179-20926-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-179-20,926 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Energy Exploration, Inc. OPERATORS LICENSE NO. 5063

ADDRESS 1002 S. Broadway, Wichita, KS 67211 PHONE # (316) 267-7336

LEASE (FARM) B.H. WERTH WELL NO. 1 WELL LOCATION SE NW ^{NE} SE COUNTY Sheridan

SEC. 15 TWP. 10S RGE. 26 (~~EXX~~(W) TOTAL DEPTH 4150' PLUG BACK TD NA

Check One:

OIL WELL _____ GAS WELL _____ D & A X SW STATE CORP WELLS DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 222' CEMENTED WITH 150 SACKS common
3%cc, 2% gel

CASING SIZE NA SET AT NA CEMENTED WITH NA SACKS

PERFORATED AT NA

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL plug w/190 sxs 60/40 pozmix, 6% gel
3% cc, 1 bag fowseal, 25 sxs @ 2250', 100 sxs and 1 bag celloflake @ 1330',
40 sxs @ 270', solid bridge w/10 sxs @ 40', 1/2 sx in the hole, 15 sxs RH

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7-15-88 Start 2:30 pm

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Dinkel PHONE # (913) 726-4875

ADDRESS Route.#2, Ellis, KS 67637

PLUGGING CONTRACTOR Warrior Drilling Co. Rig #1 LICENSE NO. 5883

ADDRESS 151 N. Main #700 Wichita, KS 67202 PHONE # (316) 262-3791

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: F.W. Shelton, Jr.
(Operator or Agent)

DATE: 7-18-88

RECEIVED
STATE CORPORATION COMMISSION
5-2-88
AUG 2 1988
CONSERVATION DIVISION
Wichita, Kansas