

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20462-00-01  
Spot: CNWSW Sec/Twnshp/Rge: 27-10S-30W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: RALPH BAALMAN Well Number: 1  
County: SHERIDAN Total Vertical Depth: 2527 feet

Operator License No.: 32794  
Op Name: DELBERT GROSS DBA RAVEN OIL  
Address: 2911 WILLOW UNIT SOUTH  
HAYS, KS 67601

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 267  
Production: Size 4.5 feet: 4524 225 sx cmt 82.13  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/14/2001 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Originally drilled in 1976 with 8 5/8" set then.  
OWWO in March of 2001. No ALT II - decision to P&A.  
Pulling unit could not pull 4 1/2" casing - moved in casing pulling rig.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/14/2001 2:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 267' w/cwc. 4 1/2" set at 4524' w/225 sxs.  
Prod Perfs 4102' - 4378' O.A.  
Sanded back to 4035' with 4 sxs common cement on sand with bailer.  
Recovered 1850' of 4 1/2" from shot by stretch.  
Mixed and pumped down 4 1/2" 100 sxs cement blend with 500# hulls mixed in.  
Started "Hydrolic Jacking" casing out of hole.  
Pulled to 300' - mixed and pumped 50 sxs to circulate to cellar.  
Pulled 4 1/2" casing.  
Topped off 8 5/8" with 15 sxs cement blend - used total of 165 sxs cement blend with 500# hulls.  
Plug complete.

INVOICED  
DATE 6-26-01  
INV. NO. 2001061982

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

RECEIVED  
(TECHNICIAN) KANSAS CORPORATION COMMISSION

JUN 26 2001 Form CP-2/3

CONSERVATION DIVISION

JUN 18 2001

DON E. PRATT  
P.O. BOX 370, HAYS, KS.

#1 RALPH BAALMAN

27-10-30W  
C NW SW

CONTR MURFIN DRLG. CO. CTY SHERIDAN

GEOL GREEN & GREEN FIELD WC (2<sup>+</sup> NW OF VERHOEFF)

E 2935 KB CM 8/18/77 CARD ISSUED 9/1/77 IP D&A/BKC 8/25/77

+	+	+
+	+	+

API 15-179-20,462

LOG	TOPS	DEPTH	DATUM
TOP	3751	- 816	
HEEB	3970	-1035	
TOR	3994	-1059	
LKC	4008	-1073	
BKC	4283	-1348	
LTD	4316	-1381	

8-5/8" 259/200sx  
DST (1) 4142-4214 (LKC)/30-30-30-30,  
60' SOCM, 3' FREE O, SIP 1026-953#  
FP 64-113#  
DST (2) 4178-4215 (LKC)/30-30-30-30,  
150' OCM W/SOME FREE O, SIP 1270-  
1157# FP 105-167#

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS