

4-032097

9-29

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

NW SW NW /4 SEC. 17, 10S, 25 W
3630 feet from S section line
4950 feet from E section line

Operator license# 3736
Operator: R.L.T. Investment
Address: St. Peter Route
Morland, Kansas 67650

Lease: Bollig Well # 1
County: Graham 141.83
Well total depth 4364 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 180 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 29 Month: September Year: 1995

Plugging proposal received from: Manny

Company: Mike's Testing & Salvage Phone:

Were: Order 250 sxs 60/40 pozmix - 10% gel - 200# hulls.
Allied Cement Company.
Order sand and common cement.

RECEIVED
STATE CORPORATION COMMISSION
10-20-95
OCT 20 1995

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

CONSERVATION DIVISION
Wichita, Kansas

Completed: Hour: 2:15 P.M. Day: 29, Month: September, Year: 1995

Actual plugging report: 8 5/8" set at 180' cwc. w/150 sxs. 4 1/2" set at 4167' with 125 sxs. O.H. 4167'+. Sanded back to 4100' with 4 sxs common cement on sand with bailer. Shots at 2100' - 1700' - 1600' - 1300' - 1139'. Recovered 1139' - mixed and pumped down 4 1/2" casing 250 sxs cement blend with 200# hulls to circulated cement. Laid down 4 1/2" casing. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 10-26-95
NY. NO. 43836

FD.