

To: 6 030898
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C E/2 SW NE, SEC. 26, T 10 S, R 25 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 9-6-78
3300 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5364
Operator: Beren Corp
Name & Address Box 723
Hays, Kansas 67601

Lease Name Wendelin Well # 1
County Graham 132.11
Well Total Depth 4065 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 305'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Kansas 67524

Company to plug at: Hour: _____ AM Day: 22 Month: June Year: 19 87

Plugging proposal received from Mark
(company name) Kelso Casing (phone) _____

were: 8 5/8 set at 305 w/225 sks 4 1/2" set at 4065' w/200 sks. Perfs 3840 -3968

Order sand and Com Cmt. Shoot and pull pipe. Order 200 sks ATL 65/35 Poz 10% Gel
2% Dical Cmt. blend 500# Hulls Allied Cmt. Co.

Wellbrock Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ Carl Goodrow
None _____

Operations Completed: Hour: 10:00 AM Day: 22 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on bottom to 3750' w/4 sks Com Cmt. on sand with
bailer. 3 shots at 2500' 1500' 1128'. Recovered 1128'.

Squeeze down 8 5/8 3 sks Hulls followed with 200 sks ATL CMT Blend w/3 sks Hulls mixed
in. Max. Psi. 700# Close in Psi. 200#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
7-16-87
JUL 16 1987

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If desired, observe this plugging.)

DATE 7-16-87
INV. NO. 17504

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow