

To: 6 030899
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 8 - 27 - 78

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corp
Name & Address Box 723
Hays, Kansas 67601

S/2 NE NW, SEC. 26, T 10 S, R 25 (W/E)
4290 feet from S section line

3300 feet from E section line

Lease Name Andrew Well # 1

County Graham 132.76

Well Total Depth 4085 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas 67524

Company to plug at: Hour: AM Day: 22 Month: June Year: 19 87

Plugging proposal received from Mark

(company name) Kelso Casing (phone) _____

were: 8 5/8 set at 302' w/225 sks 5 1/2 set at 4079 w/200 sks. PBD 4058.

Perfs 3853' - 3980' . Order sand and Com Cmt. Shoot and pull pipe.

Order 200 sks ATL 65/35 10% Gel 2% Dical 500# Hulls. Allied Cmt.Co.

Wellbrock Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)
Carl Goodrow

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 AM Day: 22 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on PBD to 3800' w/5 sks Com Cmt. on sand w/bailer.

4 Shots at 2500' 1500' 1400' 1328' Recovered 1328'.

Squeeze 8 5/8 w/300# Hulls Cmt. Blend w/400# Hulls mixed in.

Max. Psi 400#. Close in Psi 150#. Plug complete

RECEIVED
STATE CORPORATION COMMISSION

7-16-87
JUL 16 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did, did not) observe this plugging.

DATE 7-16-87

INV. NO. 17502

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow