

To: 6 030900  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 200 COLORADO DERBY BUILDING  
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corp  
 Name & Address Box 723  
Hays, Kansas 67601

API NUMBER 15- 7 - 25 - 77

NE NE NW, SEC. 26, T 10 S, R 25 W/E

4950 feet from S section line

2970 feet from E section line

Lease Name Agatha Well # 1

County Graham 132.24

Well Total Depth 4069 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 229'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 22 Month: June Year: 19 87

Plugging proposal received from Mark

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 8 5/8 set at 229' w/175 sks. 4 1/2" set at 4068 w/150 sks. Perfs 3871-75.

Order sand and Com Cmt. Shoot and pull pipe. Order 200 sks ATL

65/35 Poz 10% Gel 2% Dicol Cmt. Blend 500# Hulls. Allied Cmt. Co.

Wellbrock Water Trucks.

Plugging Proposal Received by Carl Goodrow  
 (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 22 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on bottom to 3800' w/4 sks Com Cmt. On sand

w/bailer. 5 shots at 3000 2500 1500 1300. Recovered 1231' of 4 1/2" csg.

Squeeze 8 5/8 w/4 sks Hulls followed w/140 sks ATL Cmt. Blend w/ 3 sks Hulls mixed

in. Max. Psi. 750#. Close in Psi. 400#. Plug complete

RECEIVED  
 STATE CORPORATION COMMISSION  
 7-16-87  
 JUL 16 1987

CONSERVATION DIVISION  
 Wichita, Kansas

Remarks: \_\_\_\_\_  
 (If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 7-16-87

INV. NO. 17503

Signed Carl Goodrow  
 (TECHNICIAN)

Carl Goodrow