

6030565

API NUMBER 15-065-22,235-00-00 **R**

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWSENE, SEC. 35, T. 10 S, R. 25 W

3630 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name KUOLL Well # 1

Operator: CHIEF DRUG. CO. INC.

County GRAHAM 131.63

Name & Address 905 CENTURY PLAZA BLDG.

Well Total Depth 4050 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 251' ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRUG. INC. License Number 5422

Address WICHITA, KANSAS 67202

Company to plug at: Hour: AM Day: 16 Month: 9 Year: 19 85

Plugging proposal received from HAROLD MALEY

(company name) ABERCROMBIE DRUG. INC. (phone) _____

were: 8 5/8 SET @ 251' WITH HOLE FULL OF NO LESS THAN 36 V/S. MUD AND NO LOSS OR GAIN OF FLUID. SPOT CEMENT PLUGS WITH DRILL PIPE. ORDER 190 SX. 60/40 PZ GEL 3% 8 5/8 W.P. ALLIED CEMENT CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 AM Day: 16 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 2150' BREAK CIRC. DISPLACE 25 SX.

CMT. MIX. LAY DOWN D.P. TO 1150' DISPLACE 100 SX. CMT. MIX. + 1 SX. HULLS

LAY DOWN D.P. TO 260" DISPLACE 40 SX. LAY DOWN D.P. PUSH W.P. TO

KELLY DEPTH DUMP 1/2 SX. HULLS FILL HOLE TO BASE OF CELLAR W/10 SX.

CMT. MIX. DISPLACE 15 SX. IN RATHOLE W/A JOINT OF PIPE. PLUG COMPLETE

Remarks: ANTH 2126-67 ELEV. 2471

(If additional description is necessary, use BACK of this form.)

INVOICED

OCT 04 1985

RECEIVED STATE CORPORATION COMMISSION

9-30-85

SEP 30 1985

Signed Carl Goodrow
(TECHNICIAN)

34
9-27-85
mjs

DATE _____

INV. NO. 10359

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84