

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22815-00-00  
Spot: N2NENW Sec/Twnshp/Rge: 35-10S-25W  
4950 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: PFEIFER Well Number: 1-35  
County: GRAHAM Total Vertical Depth: 4430 feet

Operator License No.: 9953  
Op Name: HARRIS OIL & GAS COMPANY  
Address: 1125 17TH STREET, STE 2290  
DENVER, CO 80202

Conductor Pipe: Size feet: 8 1/2  
Surface Casing: Size 8.625 feet: 315  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 03/12/2001 5:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 03/12/2001 8:00 AM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2200' w/25 sxs. Anhydrite 2160' - 2202'.  
2nd. Plug at 1250' w/100 sxs. Dakota 944' - 1244'.  
3rd. Plug at 365' w/ 40 sxs. Surface pipe to 315'.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

**INVOICED**  
DATE 03-15-2001  
INV. NO. 2001061510

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 15 2001  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)