

4- 041391

7-30

17 R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,043-00-00

SE SW SW /4 SEC. 08 , 10 S, 26 W
330 feet from S section line
990 feet from E section line

Operator license# 5654

Lease Kaiser well # 1-8

Operator: Rine Drilling & Expl., Inc.

County Sheridan

Address: 200 West Douglas
Suite 1050
Wichita, Kansas 67202-3010

Well total depth 4160 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 263 feet
w/170 sx.

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 5422

Address: _____

Company to plug at: Hour: 2:00A.M. Day: 30 Month: July Year: 92

Plugging proposal received from: Bill Craig

Company: Abercrombie RTD, Inc. Phone: _____

Were: Order 200 sx. cement 60/40 pozmix - 6% gel. & 1/4# flocele.
Heavy mud between all plugs. Pump cement down drill pipe.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00A.M., Day: 30, Month: July, Year: 92

Actual plugging report:

- 1st. plug @ 2270' w/25 sx.
- 2nd. plug @ 1340' w/100 sx.
- 3rd. plug @ 280' w/40 sx.
- 4th. plug @ 40' w/10 sx.
- 15 sx. in Rathole.
- 10 sx. in Mousehole.

Remarks: _____

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: _____

I did [] / did not [X] observe the plugging.

Dennis L. Hamel
Conservation Division
Wichita, Kansas

DATE 8-20-92

INV. NO. 36002

(agent)

RECEIVED
STATE CORPORATION COMMISSION
8-12-92
CONSERVATION DIVISION
Wichita, Kansas

INVOLVED

100