

6 061916

7-26

API NUMBER 15- 179-20,947 - 00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 8, T 10 S, R 26 W/EX
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT 5131
Operator License # _____
Operator: Thunderbird Drilling Inc.
Name & Address: Box 780407
Wichita, Ks. 67278

Lease Name Martin B Well # 1
County Sheridan 134.06
Well Total Depth 4125 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 256' w/190 sk

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422
Address Wichita, Ks.

Company to plug at: Hour: 5:45PM Day: 26 Month: July Year: 19 89

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Inc. (phone) _____

were: Order 185 sks 60/40 poz 6% gel 3% cal cl 1 sk f.c. and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis mud between all plugs with good
circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
8-11-89

AUG 11 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)


Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:45PM Day: 26 Month: July Year: 19 89

ACTUAL PLUGGING REPORT
1st plug at 2250 w/20 sks
2nd plug at 1350' w/100 sks 1 sk f.c.
3rd plug at 300' w/40 sks
4th plug at 40' w/10 sks
15 sks in rat hole No sks in mousehole

Remarks: Cemented by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

Signed 
(TECHNICIAN)

DATE 8-11-89
INV. NO. 25639