

PLUGGED

6 030786

API NUMBER 15-179-20, 868-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NENESW, SEC. 11, T. 10 S, R. 26 W

TECHNICIAN'S PLUGGING REPORT

2310 feet from S section line

2970 feet from E section line

Operator License # 8449

Lease Name DREILING Well # 1

Operator: McNAMES & PATTERSON

County SHERIDAN 133.58

Name & Address P.O. Box 20058

Well Total Depth 4110 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67208

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor MURFIN DRLG. Co License Number 6033

Address WICHITA, KANSAS

Company to plug at: Hour: 9:15 AM Day: 3 Month: 9 Year: 19 86

Plugging proposal received from LLOYD DELLETT

(company name) MURFIN DRLG. Co. (phone) _____

were: 8 5/8 SET @ 250' w/160 SX. WITH NO LESS THAN 36 VISMUD IN HOLE
SPOT CEMENT PLUGS w/ DRILL PIPE. ORDER 190 SX. 60/40 OR 680 EL 3 1/2
8 5/8 WIPER PLUG. BJ TITAN CMT. CO.

MAINTAIN FLUID (MUD) LEVEL BETWEEN CEMENT PLUGS & BALLANCE PLUGS
WITH MUD.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:15 AM Day: 3 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT CIRC. HOLE FROM BOTTOM LAYDOWN D.P. TO 2250'

DISPLACE WITH 25 SX. CMT MIX. TO 2150' LAYDOWN D.P. TO 1325'

WITH 100 SX. CMT. MIX + 1 SX. HULLS TO 925' LAYDOWN D.P. TO 300'

DISPLACE w/40 SX. CMT. MIX. TO 140' LAYDOWN D.P. FLUID LEVEL IN HOLE

ADJUSTED TO 40' PUSHED 8 5/8 W.P. TO 40' w/ 1/2 SX. HULLS FILLED HOLE FROM

W.P. TO BASE OF CELLAR w/10 SX. CMT. MIX. DISPLACED 15 SX. CMT MIX IN RATHW

w/JOINT OF PIPE. PLUG. COMPLETE. ELEV. 2601 KB SURF. 2234-67'

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 8 1986

SEP - 5 1986

signed Carl Goodrow
(TECHNICIAN) 9-5-86

INV. NO. 14903 OCT 13 1986

CONSERVATION DIVISION
Wichita, Kansas