

206

6 070915

API NUMBER 15- 179-21,001-0660

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 SW NE, SEC. 11, T 10 S, R 26 W/EX
2970 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name W. E. Bittel Well # 1

Operator: Energy Exploration Inc.

County Sheridan 134.87

Name & Address 1002 S. Broadway

Well Total Depth 4150 feet

Wichita, Ks. 67211

Conductor Pipe: Size 0 feet

Kenneth Dean

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number _____

Address Russell, Ks.

Company to plug at: Hour: _____ AM Day: 1 Month: May Year: 19 91

Plugging proposal received from Jack Fox

(company name) Emphasis Drilling Inc. (phone) _____

were: 8 5/8 - 210 ft. s.p. cwc w/165 sks 60/40 poz 2% gel 3% ca cl. (B.J.

Services) Marmington Well, Elv. 2597. Anhy 2229. Mud cond. 45 vis. 90 wt. 8.6 w.l.

Proposal 190 sks 60/40 poz 6% gel 3% ca cl w/1 sk f.c. Spot with drill stem. Circulate

hole heavy mud between all plugs. 25 sks at 2235 ft. 100 sks at 1320 ft. w/f.c. 40 sks

at 270 10 sks at 40-15 sks in rathole. Circulate.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:45PM Day: 1 Month: May Year: 19 91

ACTUAL PLUGGING REPORT Energy Exp ordered 190 sks 60/40 poz 6% gel 3% ca cl w/1 sk f.c.

Spotted with drill stem. Circulated hole. Heavy mud between all plugs.

1st plug at 2235 w/25 sks cement.

2nd plug at 1320 w/100 sks cement w/1 sk f.c.

3rd plug at 270 w/40 sks cement 15 sks in rathole. Circulate

4th plug at 40 w/10 sks cement. Cemented by B. J. Services

RECEIVED
STATE CORPORATION COMMISSION
5-30-91
MAY 30 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

xxxxx / did not observe this plugging.

Signed Marion J. Schmidt (TECHNICIAN)

INVOICED
DATE 6-5-91
INV. NO. 32002