

7-15

To: 6 070700
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,926-06-00
SE NW NE, SEC. 15, T 10 S, R 26 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063 Lease Name B.H. Werth Well # 1

Operator: Energy Exploration Inc. County Sheridan 134.88

Name & Address 1002 S. Broadway Well Total Depth 4150 feet

Wichita, Ks. 67211 Conductor Pipe: Size _____ feet

Kevin Howard Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Inc. License Number _____

Address 905 Centry Plaza Wichita, Ks. 67202

Company to plug at: Hour: 3:00 PM Day: 15 Month: July Year: 19 88

Plugging proposal received from Harold Dinkel

(company name) Warrior Drilling Inc. (phone) _____

were: 8 5/8" - 224' S.P. cwc w/150 sks Common 2% Gel 3% Ca Cl. By B. J. Titan

Lansing K.C. Well. No circulation problems. Elev. 2607' Anhy 2239', Mud condition 43 viscosity;

9.1 weight. 11.1 water loss. Proposal 190 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug.

Spot with drill stem, mud between all plugs. 25 sks at 2250'; 100 sks at 1330'; 40 sks at 270';

10 sks at 40'; 15 sks in rathole. (Cir)

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:00 PM Day: 15 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Ordered 190 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8"

plug. Spot with drill stem, recondition hole, mud between all plugs. 1st plug 25 sks at 2250';

2nd plug 100 sks w/f.c. at 1330'; 3rd plug 40 sks at 270'; 4th plug Hulls plug at 40' w/10 sks

cement. 15 sks in rathole (cir) By B. J. Titan

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-24-88

INV. NO. 22672

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt