

4-11

78
R

4-031705

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21,803-0000

SE SW NW /4 SEC. 17, 09 S, 23 W
2970 feet from S section line
4290 feet from E section line

Operator license# -

Lease Evergreen Project well # 18

Operator: Kansas State Fee Fund

County Graham

Address: Evergreen Project

Well total depth 3900 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 11 Month: June Year: 92

Plugging proposal received from: Carl Goodrow

Company: State P.I.R.T. II Phone: 913-628-1200

Were: Order 300 sx. 65/35 pozmix - 10% Gel. - 500# hulls.
Rush water trucks.
Cement in braden head.
Ran wireline to bottom.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [], None []

Completed: Hour: 3:00P.M., Day: 11, Month: June, Year: 92

Actual plugging report: 8 5/8" set @ 248' w/160 sx. cwc. 5 1/2" set @
3864' with 125 sx. D.V. tool @ 2200' with 295 sx. cwc. Squeezed
5 1/2" with 300 sx. 65/35 pozmix - 10% gel. w/500# hulls mixed in to
Max. P.S.I. 400#. Close in P.S.I. 150#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: GL

I did [] / did not [] observe the plugging. Carl Goodrow by E.A.D.

(agent)